



Boiler, Associated Plant and Controls Replacement

Carter Synergy act as Principle Contractor for school heating project.

Project Overview & Scope of Works

Carter Synergy delivered a comprehensive replacement package of the following equipment:

- Replaced three Adisa Duplex 500 kW boilers with two 660kW MHS Ultramax boilers, with associated pipework changes
- Replaced existing twin head pump with smaller pump
- Removed two 750 litre pressurisation tanks and control unit and replace with three 500 litre units and new independent controller. All new pipework arrangement
- Remove existing side stream filter, replace with new fully independent ENWA side stream, new pipework and pump arrangements
- Replace existing direct water heater to kitchen out of hours and replace with new ACV HeatMaster water heater
- Comprehensive controls and electrical package for all equipment.





MORE INFORMATION

visit: www.cartersynergy.com email: sales@cartersynergy.com